

TYPE 545 OSCILLOSCOPE

FACTORY CALIBRATION PROCEDURE

Quick check for long ends, unsoldered joints, wire dress, etc. Preset all pots and trimmers to mid-range, except delay line. Check to see that the crt pin connections are tight. Tighten set screws in both TRIGGER LEVEL knobs just snug enough so that the knob can be turned on the shaft. Install TEST LOAD UNIT switched to LO LOAD with the scope in upright position and turn the INTENSITY and SCALE ILLUM. controls full left (ccw). If, during the calibration there is any question concerning tolerances or limits of any of the circuits, refer to the Factory Specifications on Types 541 and 545 Oscilloscopes.

1. CHECK POWER SUPPLY RESISTANCE TO GROUND

The 100 v will be more than 400 Ω to ground, the -150 v about 3K, 225 v more than 5K Ω , 350 v more than 10K Ω , and the 500 v supply above 25K Ω . Check transformer primary for infinite resistance to ground (Pin 1, 2, 3, 4).

2. CHECK TIME DELAY RELAY

Turn the scope on and check time delay relay (15 to 45 seconds).

3. CHECK VOLTAGES AND MEASURE RIPPLE AND REGULATION

Adjust -150 v supply with -150 ADJ. Check 100 v, 225 v, 350 v, and 500 v supplies ($\pm 2\%$). Check elevated heater supplies at transformer terminals. (100 v at 22 and 23, 225 v at 27 and 28, 350 v at 9 and 16, -hv at 24 and 25.)

4. SET CAL. ADJ.

With the SQUARE-WAVE CALIBRATOR OFF adjust CAL. ADJ. for 100 v at CAL. TEST PT. Turn CALIBRATOR on. Voltage at CAL. TEST PT. must read between 45 v and 55 v. (Calibrator symmetry $\pm 10\%$).

Check power supplies for proper regulation with line at 105 v, TEST LOAD UNIT switched to HI LOAD; and also, line at 125 v, TEST LOAD UNIT switched to LO LOAD. The ripple on each supply in regulation will be as follows: -150 v, 5 millivolts; 100 v, 5 millivolts; 225 v, 3 millivolts; 350 v, 6 millivolts; 500 v, 7 millivolts. (Measured with a test scope.)

5. SET HV ADJ.

Turn scope to an upright position and adjust HV ADJ. control for -1350 v. Read at front of the 27K resistor at the forward ceramic strip located above the crt shield. This adjustment can be made conveniently on the 1200 v scale on the meter by measuring with respect to -150 v instead of ground. Turn off the scope and install shield over high voltage supply. (If protective slide rails are being used, install a modified shield.) With MAIN SWEEP TIME/CM switch at 1 MILLISEC advance STABILITY and INTENSITY controls and position the trace on the crt with the VERTICAL and HORIZONTAL POSITION controls.

6. CHECK SCALE ILLUM AND POSITIONING CONTROLS

Check the SCALE ILLUM control. Check position controls against the position-indicating neon lights. Check scope for microphonics. Align trace with horizontal graticule lines, push crt forward against graticule and tighten crt clamp. Check hv regulation by varying line from 105 v to 125 v. There should be no trace blooming.

7. SET CRT GEOM ADJ.

Insert from the SQUARE-WAVE CALIBRATOR enough signal so that only the rising and falling portions of the signal are visible within the graticule. Adjust STABILITY and TRIGGERING LEVEL controls for a stable display. (The trigger circuit has not been adjusted so if it is not possible to obtain a stable display, adjust the TRIG. SENS. and/or TRIGGERING LEVEL CENTERING pot.) Adjust GEOM. ADJ. (on F & I chassis directly below rear handle) to obtain minimum curvature of the vertical trace.

8. CHECK DISTRIBUTED AMPLIFIER BIAS

Invert scope and place a voltmeter across the grid lines of the distributed amplifier. Adjust VERTICAL POSITION to the point where there is zero volts from one grid line to the other. With the plus probe of the meter, check the cathode of each tube in the amplifier for at least one volt of bias.

9. CHECK VERTICAL AMPLIFIER BALANCE

Short crt vertical deflection plates to determine the crt electrical center. Short the grids of the 6DK6's, 6DJ8's, and the 12BY7's, in that order. The unbalance should not exceed 2 mm in the 6DK6 stage, 1 cm in the 6DJ8 stage, and 1 cm in the 12BY7 stage with the overall amplifier unbalance not to exceed 1.5 cm. Adjust the graticule positioning cam to align the graticule center line with the center of the usable area of the crt.

10. CHECK VERTICAL COMPRESSION OR EXPANSION

Position 2 cm of calibrator signal up and down within the graticule lines. Allowable compression or expansion is ± 0.5 mm.

11. SET VERTICAL GAIN ADJ.

Switch TEST LOAD UNIT to 250:1 and apply a 100 v signal from SQUARE WAVE CALIBRATOR and adjust AMPL. GAIN for 4 cm of vertical deflection. Switch SQUARE-WAVE CALIBRATOR to 0.2 v, TEST LOAD UNIT to 1:1 and check for 2 cm of vertical deflection.

12. CHECK ALTERNATE SWEEP OPERATION

Check scope for ALTERNATE SWEEP operation by switching TEST LOAD UNIT to DUAL TRACE. Remove the TEST LOAD UNIT and install a 53/54K PLUG-IN UNIT.

13. CHECK SQUARE-WAVE CALIBRATOR AND VOLTS TO MILLIVOLTS DIVIDER.

Check accuracy of SQUARE-WAVE CALIBRATOR voltage steps with the K UNIT VOLTS/CM step switch. Compare the VOLTS range to the MILLIVOLTS range.

14. ADJUST DC SHIFT COMPENSATION

Vertically deflect the trace with enough dc voltage to move the trace about 4 cm. This is a very slow drift and must be watched for a few seconds to see the direction of drift.

15. SET TRIGGERING LEVEL CONTROL

Set the trigger controls to +INT and DC, TIME/CM to 100 μ sec, STABILITY full left (ccw), but not to PRESET. Set the test scope VERTICAL INPUT to .05 VOLTS/CM, DC, set the trigger on LINE, AUTOMATIC and set the sweep TIME/CM switch to 1 MILLISEC, X2. Use a 10X probe properly adjusted. Center the trace on the test scope for a zero reference. Connect the probe to the grid end of the 470K resistor from the arm of TRIGGERING LEVEL pot on scope under calibration and set pot to zero volts. Physically center knob and tighten set screw. Leave TRIGGERING LEVEL control at zero volts during succeeding adjustments.

15. (cont.)

Now repeat the last step only this time put the probe on the grid end of the 1 meg resistor from the center arm of the DELAYING SWEEP TRIGGERING LEVEL control and set the knob for zero volts. (This setting is done at this time for convenience and has nothing to do with MAIN SWEEP triggering.)

16. SET INT. TRIG. DC LEVEL CONTROL

Position the trace of the scope under calibration to the center of the graticule. Re-check the test scope zero reference and connect the probe to R8, 47 Ω to pin 7 of V8. This point should be at zero volts. Now switch the scope under calibration from +INT to -INT and adjust INT. TRIG. DC LEVEL ADJ. for zero volts as indicated on the test scope.

17. ADJUST TRIGGER LEVEL CENTERING

Set TRIGGERING MODE switch to AC SLOW and TRIGGER SLOPE switch to +LINE. Switch test scope VOLTS/CM switch to 0.2 VOLTS/CM, AC. Connect probe to pin 6 of V20, on scope under calibration, and adjust TRIGGERING LEVEL CENTERING so that the waveform on the test scope is symmetrical. For final adjustment switch test scope MAGNIFIER, ON and horizontally center switching portion of the multi waveform. Now switch the TRIGGER SLOPE switch, of the scope under calibration, back and forth from +LINE to -LINE and at the same time re-adjust TRIGGERING LEVEL CENTERING until there is no horizontal shifting of the switching portion of the multi waveform.

18. ADJUST TRIGGER SENS.

Turn the TRIG. SENS. pot to the right (cw) until oscillation occurs at the leading and trailing edges of the multi waveform. (Test scope probe should still be as in STEP 16.) Note the amplitude of the spike on the waveform just at the point of oscillation. Now turn the TRIG. SENS. left (ccw) until this spike is slightly less than one-half (0.5) of the original size.

19. ADJUST PRESET STABILITY

Use 100 μ sec/cm. Turn TRIGGERING MODE to AUTOMATIC, +LINE. Turn the PRESET STABILITY control clockwise until the sweep triggers. The center arm of the control should read about 80 v on a meter. Now continue turning PRESET STABILITY until the sweep free-runs (trace will brighten), the center arm on the control should be between 15 v and 25 v higher. Turn the control back until the meter reads half way between the two readings obtained.

20. CHECK TRIGGER CIRCUIT FOR PROPER OPERATION

Obtain 2 mm of vertical deflection from the calibrator and see that the trigger circuit will work properly in all positions, except LINE and HF SYNC, of the TRIGGER SLOPE and TRIGGERING MODE switches.

21. ADJUST DELAY LINE AND HF COMPENSATIONS

With the VOLTS/CM switch at 0.05, variable VOLTS/CM control full right (cw), insert into the K UNIT from a properly terminated fast rise-time square-wave generator, a 400 kc signal of about two or three cm of vertical deflection. A Type 53/54 P UNIT can also be used. Switch the MAIN SWEEP TIME/CM to 1 μ SEC, X5. Adjust the trimmers in the delay line with an insulated tool for optimum square-wave response. The variable coils control the amount of spike on the leading edge of the waveform.

22. MEASURE VERTICAL RESPONSE

Measure the bandwidth with a constant amplitude sine-wave generator, for example, Tektronix Type 190. Turn the generator to 2 mc and insert enough signal for 3 cm

22. (cont.)

of vertical deflection, increase the frequency to 30 mc. The signal should still be at least 2.1 cm in amplitude.

23. CHECK HF SYNC.

Turn the signal generator to 30 mc, switch TRIGGERING MODE to HF SYNC. A stable display should be obtained with about 2 cm or less of vertical deflection by adjusting the MAIN SWEEP STABILITY.

24. ADJUST SWEEP CAL.

Apply 1 millisecc time marks to INPUT. Turn HORIZONTAL DISPLAY to DELAYING SWEEP, DELAY SWEEP TIME/CM switch set to 1 MILLISEC. Jumper the TRIGGER or EXT. SWEEP IN to VERTICAL SIG. OUT and adjust STABILITY and TRIGGERING LEVEL for a stable display. Adjust SWEEP CAL. for one time-mark per cm. When any timing adjustments are made always make them from the 1 cm line to the 9 cm line on the graticule.

25. ADJUST MAIN-SWEEP TO DELAYING-SWEEP TIMING

Switch HORIZONTAL DISPLAY to MAIN SWEEP, MAIN SWEEP TIME/CM at 1 MILLISEC and adjust R99M to match delaying sweep timing within .5%. (R99M is on the MAIN SWEEP TIME/CM Bracket.)

26. ADJUST R64

Set HORIZONTAL DISPLAY on MAIN SWEEP DELAYED with DELAYING SWEEP STABILITY full right (cw), set MAIN SWEEP TIME/CM switch to 100 μ SEC. Turn the MAIN SWEEP STABILITY control until a trace first appears. Connect a test scope through a 10X probe to pin 8 of V37 and observe a composite sawtooth and gate waveform. Adjust R64 to the point where the sawtooth portion of the waveform is about two-thirds of the amplitude of the gate portion. The gate portion of the waveform must be at least 9 v in amplitude. Each time the setting of R64 is changed, readjust the MAIN SWEEP STABILITY as above or an erroneous adjustment of R64 will result. Recheck Step 19.

27. ADJUST MAIN SWEEP LENGTH

Adjust MAIN SWP LENGTH control for approximately 10.5 cm of horizontal sweep.

28. ADJUST MAG GAIN

Turn MAIN SWEEP TIME/CM switch to 1 MILLISEC and insert 1 millisecc and 100 μ sec markers from the time-mark generator. Turn MAGNIFIER, ON and adjust MAG GAIN for 5X magnification. (1 large mark every 5 cm and 2 small marks every cm.) Check magnifier linearity over the entire sweep length.

29. ADJUST SWP/MAG REGIS.

With MAGNIFIER ON, position the trace so that the first time mark falls on the center line of the graticule. Turn MAGNIFIER, OFF and adjust SWP MAG/REGIS., so that the first time mark again falls on the center line of the graticule. Check to see that the MAG. ON and MAG. OFF positions register properly in the middle and at the end of the sweep.

30. ADJUST EXT SWP AMPL DC BAL.

Turn MAG on. Connect MAIN SWEEP SAWTOOTH into vertical INPUT and switch HORIZONTAL DISPLAY to EXT. SWEEP. Adjust EXT. SWP. AMPL. DC BAL. for no horizontal shift of vertical trace when turning EXT. SWEEP ATTEN. back and forth.

31. ADJUST EXT SWP AMP COMP.

Apply a fast rise square wave (about 2 kc) to EXT. SWP. IN. With MAGNIFIER ON, externally trigger sweep. Adjust C240 (this will be a long time-constant compensation) for optimum square-wave response. Turn MAGNIFIER, OFF and adjust C254 (short time constant). Adjust C267, mica trimmer on the pot bracket. (Very fast time-constant). C254 and C267 will be adjusted again for a linear sweep using a 10 mc sine wave. Turn MAG on. Now connect the square wave thru a standard 47 μ f probe into EXT. SWP. IN and adjust C110 for optimum flat top. Adjust EXT SWEEP 10X ATTEN. compensation C100 and C101. Check slope switch for correct polarity (plus is left).

32. CHECK EXT. SWEEP IN DEFLECTION FACTOR

With 0.2 v of calibrator signal fed into the EXT. SWEEP IN, EXT SWEEP ATTENUATOR switch X1, variable control full right (cw) MAG ON at least one cm of horizontal deflection must be observed. Increase calibrator signal to 2 v, switch the attenuator to X10 and check X10 attenuator accuracy ($\pm 2\%$).

33. CHECK MAIN SWEEP RATES

Check the MAIN SWEEP rates as follows:

<u>TIME/CM</u>	<u>MULTIPLIER</u>	<u>TIME MARK GEN.</u>	<u>ACTION</u>
<u>100 μsec</u>	<u>X1</u>	1 millisc	check sweep rate
<u>100 μsec</u>	<u>X2</u>	1 millisc	check multiplier
<u>100 μsec</u>	<u>X5</u>	1 millisc	check multiplier

34. CHECK MAIN SWEEP VARIABLE MULTIPLIER CONTROL

Check MULTIPLIER on the 2.5-1, 5-2, 12-5 positions for sufficient range.

<u>10 MILLISEC</u>	<u>X1</u>	10 millisc	check sweep rate
<u>100 MILLISEC</u>	<u>X1</u>	100 millisc	check sweep rate
<u>1 SEC</u>	<u>X1</u>	1 sec	check sweep rate
<u>1 SEC</u>	<u>X2</u>	1 sec	check multiplier
<u>1 SEC</u>	<u>X5</u>	1 sec	check multiplier

35. ADJUST MAIN SWEEP TIMING

Adjust the fast MAIN SWEEP rates timing as follows:

10 μ SEC	X1	10 μ sec	adjust C99F
1 μ SEC	X1	1 μ sec	adjust C99H
1 μ SEC	X2	1 μ sec	check MULTIPLIER
1 μ SEC	X5	5 μ sec	check MULTIPLIER
.1 μ SEC	X5	1 μ sec	adjust C99J Position first marker to left off graticule.
.1 μ SEC	X1	10 mc	adjust for linearity C254 and C267
.1 μ SEC	X1 MAG ON	50 mc	adjust for linearity C278 and C286

There will be interaction between the linearity adjustment of C267 and C254 and the timing adjustments of C99H and C99J so it will be necessary to it will be necessary to go back and readjust these steps over again until the timing is correct.

36. SET DELAYING-SWEEP LENGTH

Switch HORIZONTAL DISPLAY to DELAYING SWEEP, TIME/CM to 500 μ SEC and install the

36. (cont.)
DELAYING SWEEP, LENGTH control limiting resistors. R181B (usually 12K to 18K) shunt the length control. R182B (usually 47K to 68K) shunts the 12K resistor between the length control pot and -150 v.

37. SET DELAY START ADJ AND DELAY STOP ADJ.

Use 500 μ sec/cm delaying sweep speed; 10 μ sec/cm Main Sweep Speed. From the time-mark generator feed 500 μ sec marks to the INPUT. Trigger the DELAYING SWEEP by feeding from VERT. SIG. OUT with a jumper into TRIGGERING IN. Adjust STABILITY and TRIGGERING LEVEL for a stable sweep. Turn MAIN SWEEP STABILITY full right (cw) to free-run sweep. ^{Set} Check DELAY-TIME MULTIPLIER to 1.00. Adjust DELAY START ADJ. till the bright portion just reaches the first time mark. Turn the MULTIPLIER to 9.00 and adjust DELAY STOP ADJ. so that the bright spot reaches the ninth time mark. There will be interaction between these adjustments so it will be necessary to go back and forth several times. Switch HORIZONTAL DISPLAY to MAIN SWEEP DELAYED and make final adjustments. Check linearity of the DELAY-TIME MULTIPLIER at all major divisions.

38. CHECK DELAYING-SWEEP RATES

When timing or checking any other than 500 μ sec ranges of the DELAYING SWEEP first turn the DELAY TIME MULTIPLIER to 1.00 and notice the error in delay start, this is due to the trigger circuit. Now turn the DELAY TIME MULTIPLIER back to 9.00 plus the error noted at 1.00. When adjusting or checking the faster sweep ranges this trigger error may be as much as 15 minor divisions.

<u>DELAY SWEEP TIME/CM</u>	<u>TIME MARK GEN.</u>	<u>HORIZONTAL DISPLAY*</u>	<u>MAIN SWEEP TIME/CM</u>
<u>200 μSEC</u>	100 μ sec	MAIN SWEEP DELAYED	<u>10 μSEC</u>
<u>500 μSEC</u>	500 μ sec	MAIN SWEEP DELAYED	<u>10 μSEC</u>
<u>1 MILLISEC</u>	1 millisecond	MAIN SWEEP DELAYED	<u>10 μSEC</u>
<u>5 MILLISEC</u>	5 millisecond	MAIN SWEEP DELAYED	<u>100 μSEC</u>

39. ADJUST DELAYING-SWEEP RATES

<u>50 μSEC</u>	C190D	50 μ sec	MAIN SWEEP DELAYED	<u>1 μSEC</u>
<u>5 μSEC</u>	C190F	5 μ sec	MAIN SWEEP DELAYED	<u>1 μSEC</u>

Check all delay sweep rates for operation.

* Make rough adjustments in DELAYING SWEEP

40. CHECK DELAY TIME MULTIPLIER LINEARITY

Check DELAY TIME MULTIPLIER on 50 μ SEC and 5 μ SEC ranges for linear sweep. (two minor-division error allowed from 1.00 to 9.00).

41. CHECK MAIN SWEEP DELAYED JITTER

Set the DELAYING SWEEP TIME/CM control to 1 MILLISEC, and MAIN SWEEP TIME/CM to 1 μ SEC. Display 1 millisecond markers with the HORIZONTAL DISPLAY control at DELAYING SWEEP. Set the DELAY-TIME MULTIPLIER so that the brightened portion of the sweep coincides with the marker at the 1 cm graticule line. Switch the HORIZONTAL DISPLAY control to MAIN SWEEP DELAYED. The horizontal jitter should not exceed 2 mm. Repeat the process at the 9 cm graticule line, jitter at this position should not exceed 4 mm.

42. CHECK RESET MAIN SWEEP AND READY NEON

With HORIZONTAL DISPLAY in MAIN SWEEP normal display about 2 cm of vertical deflection from the calibrator and set STABILITY and TRIGGERING LEVEL controls for a stable trace. The READY-light should not be on. Switch HORIZONTAL DISPLAY to

42. (cont.)

MAIN SWEEP DELAYED, and turn DELAY SWEEP STABILITY left (ccw). Press the RESET MAIN SWEEP button. A single trace should occur. If the calibrator signal is removed, instead of a single trace the READY light will ignite when the RESET MAIN SWEEP button is pressed, then when a signal is fed to the INPUT a trace will be triggered and a single trace will occur and the light will go out.

Re-check steps 19 and 26.

43. CHECK MAIN-SWEEP HOLD-OFF

Connect a probe from test scope, set for DC input, to the right-hand end of C240. Set MAIN SWEEP STABILITY full right (cw). Check all ranges of MAIN SWEEP TIME/CM switch for sufficient hold-off.

44. CHECK DELAYING-SWEEP HOLD-OFF

Now switch HORIZONTAL DISPLAY to DELAYING SWEEP and repeat the last step.

45. CHECK FRONT PANEL WAVEFORMS

With a test scope set for DC input, using a 1X (straight through) probe, check +GATE MAIN SWEEP for a gate waveform of about 20 v amplitude with its base on the zero-volt reference line on the test scope. SAWTOOTH MAIN SWEEP should be about 150 v in amplitude with its base line on a zero reference, except on the two fastest speeds where its base line should raise about 20 v. DEL'D TRIG. from MAIN or DEL'G SWEEP should be a spike of at least 5 v on all sweep rates. +GATE DEL'G SWEEP, 20 v, zero reference. Out of the VERT. SIG. OUT there should be 2 v of signal for every cm of vertical deflection on the scope under calibration. There should be 6.3 v of ac voltage out of binding post, labeled 6.3 V 1A AC. This can be checked with the test scope or a meter.

46. CHECK CRT CATHODE INPUT

Remove CRT CATHODE GND. strap from rear of scope and insert signal from calibrator and check sweep for intensity modulation. With normal intensity, 20 v of calibrator signal will modulate the trace.

47. MAKE A NOTE OF CRT TYPE AND SERIAL NUMBER AND RECORD ON CALIBRATION RECORD.

